



Schneider & Son, Inc.

P.O. Box 258 Yacolt, WA 98675 (360)409-9781 WA LIC: SCHNESI829JS WA UDBE: D4M0021778

BID BREAKDOWN

GLOCKENSPIEL BELLS CITY HALL

ITEM	QUANTITY	UOM	DESCRIPTION	UNIT PRICE	TOTAL
1	1	LS	ELECTRICAL WORK GLOCKENSPIEL BELLS CITY HALL	\$43,428.93	\$43,428.93
BID TOTAL:					\$43,428.93

BREAKDOWN

Labor:	\$21,242.00
Material:	\$14,585.00
Equipment:	\$4,572.00
Tax:	\$3,029.93

Includes:

- Remove Existing Control Panel
- Remove Existing Wires and Conduit from Control Panel to Tower
- Install Panel Supplied by Verdin
- Install Disconnect with Conduit and Wire
- Install Wire from Main Electrical Panel to Control Panel
- Install Surface Mount Outlets Near Control Panel
- Install EMT from Control Panel to Tower for Clock and Lights
- Install Junction Box in Tower with Non Metallic Flex to Clock and Lights
- Install Separate Circuits for Clocks and Lights from the Control Panel to Tower
- Install EMT from Control Panel to Tower for Strikers
- Install Junction Box in Tower with Non Metallic Flex to Each Striker
- Install Stranded #12 Wire from Control Panel to Strikers
- Install Control Wire from Panel to Supreme
- Label all Wires Per Verdin
- Wire Control Panel Per Verdin
- Support Verdin with Field Testing and Turn on
- Tax

Clarifications & Bid Exclusions:

- Bond

Schneider & Son, Inc., Rick Schlecht
RickS@Schneiderandson.com

Date: 9/19/2022