

**CHANGE ORDER**

Change Order No.: 2

Date of Issuance: **7/10/2020**  
 Owner: **City of White Salmon, Washington**  
 Contractor: **Crestline Construction Company, LLC**  
 Engineer: **Anderson Perry & Associates, Inc.**  
 Project: **Jewett Water Main Improvements**

The Contract is modified as follows upon execution of this Change Order:

Description of Changes (Supplemental description, Plans and Specifications attached, as applicable)		DECREASE in Contract Price	INCREASE in Contract Price
2-1	Replacement of Storm Drain Impacted by Construction	\$0.00	\$23,500.00
Subtotal		\$0.00	\$23,500.00
Total, Increase Less Decrease		\$23,500.00	
Sales Tax (7.5%)		\$1,762.50	
Net Change in Contract Price for this Change Order		\$25,262.50	

**JUSTIFICATION:**

Work was needed to restore existing storm drain system impacted by water main installation. Existing storm drain pipe was too deteriorated to make a sound connection. Competent storm drain pipe was not found before reaching the catch basin on the north and east side (approx. STA A17+18) (see attached Field Order No. 2 for additional details). Work included 166 linear feet of 12-inch diameter C-900 pipe and two catch basins. Cost was agreed to be on a lump sum basis, including all materials, labor, and equipment except for surface restoration, which will be paid by appropriate unit price items.

The amount of the Contract will be increased for this Change Order by the sum of:

\$25,262.50

Total Contract Price prior to this Change Order:

\$2,319,810.23

The Contract Price incorporating this Change Order:

\$2,345,072.73

Contract Times prior to this Change Order:

Date of Substantial Completion:

September 16, 2020

Date Ready for Final Payment:

October 16, 2020

The Contract period provided for Substantial Completion will be increased.

5 days

Revised Date of Substantial Completion:

September 21, 2020

Revised Date Ready for Final Payment:

October 21, 2020

**RECOMMENDED:**

By: David Jensen  
Anderson Perry & Associates, Inc.

Title: Project Engineer

Date: July 10, 2020

**ACCEPTED:**

By: Lucy Johnson for Nick Jacob  
Crestline Construction Company, LLC

Title: Project Manager

Date: 7/10/20

**ACCEPTED:**

By: \_\_\_\_\_  
City of White Salmon, Washington

Title: \_\_\_\_\_

Date: \_\_\_\_\_

**Approved by Agency:**

By: \_\_\_\_\_  
USDA Rural Development

Title: \_\_\_\_\_

Date: \_\_\_\_\_

**FIELD ORDER**

Field Order No. 2

Date of Issuance: **May 19, 2020**  
Owner: **City of White Salmon, Washington**  
Contractor: **Crestline Construction, LLC**  
Engineer: **Anderson Perry & Associates, Inc.**  
Project: **Jewett Water Main Improvements - 2019**

Contractor is hereby directed to promptly execute this Field Order, issued in accordance with General Conditions Paragraph 11.01.A.3, for minor changes in the Work without changes in Contract Price or Contract Times. If Contractor considers that a change in Contract Price or Contract Times is required, submit a Change Proposal before proceeding with this Work.

Reference: \_\_\_\_\_ **Drawing C-102**  
Specification(s) Drawing(s) / Detail(s)

**Description:** Remove and replace the existing 12-inch diameter storm drain pipe on the south side of W Jewett Boulevard from the southwest intersection of SW Riverwatch Drive and W Jewett Blvd until a connection can be made to competent pipe west of the catch basin in front of 107 W Jewett Boulevard (approximately STA A7+15). In addition, remove and replace the storm drain pipe that originates from the north at approximately STA A6+15 and transverses Jewett Boulevard. Install a new catch basin on this line at the intersection of the two new storm drain pipes. The pipe shall be C900 PVC pipe or approved equal. The catch basin frame and cover shall be American Iron and Steel (AIS) compliant.

This Work shall be paid through a Change Proposal and Change Order approved by the Owner, Engineer, and Agency. All surface restoration associated with the Work shall be paid by unit prices.

This Work is required due to the discovery of a buried catch basin blocking the water main installation on SW Riverwatch Drive. During the removal of this catch basin and the piping to its east, the existing storm drain pipe was not found to be competent and required removal. A new catch basin and storm drain pipe is needed for the Owner to clean the line leading to the north catch basin.

**Attachments:** Storm drain and catch basin improvements.

ISSUED: \_\_\_\_\_ RECEIVED: \_\_\_\_\_  
By: David Jones By: [Signature]  
Engineer (Authorized Signature) Contractor (Authorized Signature)  
Title: Project Engineer Title: Project Engineer  
Date: May 19, 2020 Date: 5/20/20

Copy to: Owner